

## CONTENTS

1.0	INTRODUCTION	1
2.0	RELATED CLOSED-CYCLE GAS TURBINE BACKGROUND	3
2.1.	Closed-Cycle Gas Turbine Operating Experience	4
2.2.	Closed-Cycle Gas Turbines with Air as Working Fluid	4
2.2.1.	Escher Wyss Plant	4
2.2.2.	2.3 MWe Ravensburg Plant	4
2.2.3.	6.6 MWe Coburg Plant	7
2.2.4.	13.75 MWe Oberhausen I Plant	7
2.2.5.	6.4 MWe Haus Aden Plant	11
2.2.6.	17.25 MWe Gelsenkirchen Plant	11
2.2.7.	30 MWe Spittelau Plant	14
2.3.	Closed-Cycle Gas Turbines with Helium as the Working Fluid	14
2.3.1.	The La Fleur Helium Turbine Process Plant	14
2.3.2.	Escher Wyss Helium Gas Turbine for La Fleur Process	16
2.3.3.	50 MWe Oberhausen II Helium Turbine Plant	21
2.4.	Activities in Support of Nuclear Gas Turbine Development	23
2.4.1.	High Temperature Helium Test Facility (HHV)	23
2.4.2.	Steam Cycle HTGR Helium Component Development	24
2.4.2.1.	Helium Axial Flow Circulator	24
2.4.2.2.	Steam Generator for HTGR Plant	28
2.5.	Summary	28
	References	32
3.0	NUCLEAR GAS TURBINE INCENTIVES AND BENEFITS	38
3.1.	Incentives and Motivation	38
3.2.	GT-HTGR Plant Benefits	43
3.2.1.	Low Power-Generation Cost	43
3.2.2.	High Reliability and Availability	47
3.2.3.	Flexibility in Plant Siting	47
3.2.4.	Inherent Safety	47
3.2.5.	Minimum Environmental Impact	50
3.2.6.	Conservation of Resources and High Cost Benefit	50
3.2.7.	Application of Reject Heat	50
3.2.8.	Flexibility in Plant Rating	51
	References	55
4.0	BACKGROUND OF GT-HTGR DESIGN STUDIES	56
4.1.	Thermodynamic Cycle and Performance	56
4.1.1.	Thermodynamic Cycle	58
4.1.2.	Major Cycle Parameters	64
4.1.3.	Plant Performance	65
4.1.4.	Performance Potential	68
4.2.	GT-HTGR Plant Configuration Studies	76
4.2.1.	Plant Configurations with Vertical Turbomachinery	79
4.2.2.	Plant Configurations with Horizontal Turbomachinery	89
4.2.2.1.	Initial Configuration with Horizontal Turbine	91
4.2.2.2.	Selected Configuration with Horizontal Turbine	91
	References	114

5.0	GT-HTGR REFERENCE PLANT DESIGN	115
5.1.	Optimization Studies	115
5.2.	Thermodynamic Cycle and Performance	115
5.3.	Primary System Design	119
5.4.	Prestressed Concrete Reactor Vessel (PCRVR)	129
5.5.	Component Design	135
5.5.1.	Turbomachinery	135
5.5.2.	Heat Exchanger Design	138
5.6.	Maintenance Considerations	145
5.7.	Overall Plant Configurations	147
5.8.	Summary	151
	References	152
6.0	COMPONENT DESIGN CONSIDERATIONS	153
6.1.	Turbomachine Design	153
6.1.1.	Compressor Aerodynamic Design Considerations	153
6.1.2.	Turbine Aerodynamic Design	164
6.1.3.	Turbomachine Mechanical Design	166
6.1.4.	Turbomachine Installation and Removal	175
6.1.5.	Rating Potential for 60 Hz Turbomachine	175
6.1.5.1.	Blade Stresses	175
6.1.5.2.	Material Properties	177
6.1.5.3.	Turbomachine Size Limits	179
6.1.5.3.1.	Nickel-Base Blade Material	179
6.1.5.3.2.	Refractory Blade Material	179
6.2.	Heat Exchanger Design Considerations	179
6.2.1.	Recuperator Design	185
6.2.2.	Precooler Design	190
6.2.3.	Heat Exchanger Fabrication Considerations	199
6.2.4.	Heat Exchanger Installation, Handling, & Maintenance	202
6.2.5.	Heat Exchanger Economic Considerations	204
6.2.6.	Heat Exchanger Design Summary	204
6.3.	Control Valve Design	206
6.4.	Materials Testing Program	211
	References	215
7.0	SECONDARY POWER CYCLE (BINARY PLANT)	216
7.1.	Working Fluid Selection	216
7.2.	Secondary Power Cycle Conditions	219
7.3.	Component Design Considerations	222
7.3.1.	Ammonia Turbine Design	222
7.3.2.	Turbine-Driven Ammonia Feedpump	232
7.3.3.	Condenser Conceptual Design	237
7.4.	Secondary Power Cycle Building Layout	242
7.5.	Summary of Secondary Power Cycle Design Studies	242
	References	245

8.0	DEVELOPMENT AND TESTING ALTERNATIVES	247
8.1.	Helium Component Test Facility (HCTF)	247
8.2.	Nuclear PCL Testing in a Demonstration Plant	247
8.3.	Temporary Helium Heater Approach	253
8.4.	Subcomponent Test Approach	253
8.5.	Development Needs Common to Fossil-Fired and Nuclear Closed-Cycle Gas Turbines	254
9.0	RELATED INTERNATIONAL NUCLEAR CLOSED-CYCLE GAS TURBINE PROGRAMS	254
10.0	SUMMARY	257
	ACKNOWLEDGEMENTS	258